



Update on the Magdalena Ridge Observatory Interferometer

M.J. Creech-Eakman

New Mexico Tech – MROI Proj. Scientist

On behalf of the NMT and Cambridge Teams


Magdalena Ridge Observatory

- Federally funded 2000-2011
- EIS completed in 2003
- Two facilities at MRO
 - Fast-tracking 2.4m
 - NIR/Optical 10-element interferometer
- 2.4m scope started full operations Aug, 2008
- Primarily NASA/DoD funded

- MROI is 10 1.4m movable afocal telescopes in equilateral Y configuration
- Optical and near-IR operation
- Baselines from 7.8 to 340m
- Design optimized for imaging mission

MROI Key Science Mission


- AGN:
 - Verification of the unified model.
 - Determination of nature of nuclear/extra-nuclear starbursts.
 - $H = 14$ gives > 100 targets.
- Star and planet formation:
 - Protostellar accretion, imaging of dust disks, disk clearing as evidence for planet formation.
 - Emission line imaging of jets, outflows and magnetically channeled accretion.
 - Detection of sub-stellar companions.
- Stellar accretion and mass loss:
 - Convection, mass loss and mass transfer in single and multi-star systems.
 - Bipolarity and collimation of circumstellar material, wind and shock geometries.
 - Pulsations in Cepheids, Miras, RV Tauris, etc.



Technical Requirements Flowdown


- Telescope diameter of 1.4 m
 - H magnitude = 14th for group delay tracking limit
- Spatial scales of 0.3 to 30 mas
 - Baselines from 7.8 to 340 m (for 0.6-2.4 microns)
- Moderate-to-high spectral resolutions
 - Separate fringe tracking and science cameras
- High throughput to achieve sensitivity limit
 - Fifteen reflections from primary to detectors
 - Optimized coatings for 0.6-2.4 microns
- Large number of telescopes rapidly combined
 - Optimized for model-independent imaging

Walk through the Optical Path





Unit Telescopes

- Designed/built by AMOS
 - 1.4m aperture
 - afocal alt-alt design
 - polarization preserving
 - 62 nm rms wavefront after three reflections
 - UT1 expected to arrive next year
 - UT2-3 long-lead items ordered and being assembled






Optics & UT Enclosures

- Enclosures Designed by EIE
- Houses and transports UTs
- Allows close-packed configuration to 30 deg elevation without vignetting for 6 hour tracks
- 6 full sets of optics in house
 - All M2's and M3's completed
 - First 3 M1's in various states of completion





Fast Tip-tilt & Acquisition System

- At an advanced stage of construction in Cambridge:
 - Full-scale prototype under test
 - Majority of software complete
- Uses Andor EM CCD head
- Transmissive optics
 - High throughput and relaxed tolerances
- Fully passive opto-mechanical design:
 - No actuation to meet stability requirements
- V-band sensitivity of 16:
 - Good match to reddest targets



Foundations and Beam Relay System



completely
d by M3 and built

ingent thermal,
ility and
e requirements

3 UTs per
with 0.5 mbarr
om UT to BCA

piers for inner
an 2010

all components of
d alignment



Inner Array Install





5 piers installed with infrastructure being added as funds become available





Automated Alignment System

- Designed and built by



experiment –
poster upstairs





Beam Combining Facilities

- Design by M3/built KL House – delivered in 2008
- Thermal & vibrational stability
- Supports full array
- Single-pass DL section 190 m long



Delay Lines



- Designed/built Cambridge
- Innovative approach
- Inductive pick-up & wireless communications
- DLI install to about 100m
 - <0.5mm subsidence over 1 year
 - <0.5'' metrology pointing stability over weeks







Fringe Tracker - ICoNN

- Designed/built by MRO
- Operates H or Ks
- Coatings designed in-house
- Uses nearest-neighbors combination
- Dewar arrived last fall
- CLFE Poster upstairs



Science Instrument - SIRCUS

- MRO conceptual design phase
- J,H,K with $R \sim 30$ and 300; studying higher R
- Potential design: 4-way image plane combination with fast-switching to combine 6 beams in ~ 100 sec



Mag	J	H	K
13	0.45	0.54	0.53
11	17.6	20.8	18.4
9	195	207	159


Performance:
 SNR per spectral
 channel in 100 sec
 at $R \sim 30$ with 0.7"
 seeing and $RN=5e-$

Software infrastructure

- Architecture and Framework:
 - Centralized Supervisory System controls distributed systems
 - Automatic Interface code generation based on sub-system descriptions
 - Sub-system s/w developed in Java or C
 - Standalone testing of sub-system s/w
 - **Comprehensive simulation framework**

- Status of major sub-system software:

- UT mount complete (via simulator)
- WAS complete
- Environmental Monitoring System complete
- **FTT in development**
- **Fringe Tracker system in development**
- **Enclosure software designed, not yet implemented**



Funding & Schedule Issues



- Need \$45M over next 6.5 years to get 4 telescope facility operational – mix of Federal, State, institutional, philanthropic and partner funding
- Have DOT fund to build a visitor center and maintenance facility on Ridge → allow testing of UTI
- No more Federal earmarks*
- Currently operating on university bond funds
- Plans to go for State Funding:
 - Applying for Severance Bond in Jan 2013 Session (Attain first fringes in 3Q 2015)
 - Applying for GO Bond in Nov 2013 (Add UT3 capabilities in early 2016)
- Plans to pursue Mid-Scale funding after first fringes
- **Looking for university or potential consortium partners**

Thank you for your attention!

- PI: Van Romero
- Deputy PI: R. Cervantes
- Prog. Director: I. Payne
- System Architects: C. Haniff, D. Buscher
- Proj. Scientist: M. Creech-Eakman
- Proj. Manager: R. Selina
- NMT Team: M. Edwards, A. Farris, D. Klinglesmith, T. McCracken, A. Olivares, C. Salcido, A. Shtromberg, a few student assistants
- Cam. Team: R. Boysen, J. Coyne, M. Fisher, B. Seneta, D. Sun, D. Wilson, J. Young

