



# The expanded Long Wavelength Array Greg Taylor (UNM)

#### New Mexico Symposium November 6, 2015

http://lwa.unm.edu



#### The LWA Radio Observatory Staff (at UNM)



Faculty and Staff Trish Henning Greg Taylor John Dickel HAL

Jayce Dowell Lanie Dickel

Postdocs and Students Karishma Bansal Joe Malins

Veronica Dike Jessica Lopez

Frank Schinzel Kevin Stovall



10-88 MHz usable Galactic noise-dominated (>4:1) 24-87 MHz 4 independent beams x 2 pol. X 2 tunings each, 2 degrees wide at 80 MHz SEFD ~ 6 kJy (zenith)  $S_{min}$  ~ 10 Jy (5 $\sigma$ , 1 s, 16 MHz, zenith) All sky (all dipoles) modes: TBN (70 kHz-bandwidth; continuous) TBW (78 MHz-bandwidth, 61 ms burst) LWA1 science emphasis: transients, pulsars, Sun, Jupiter & Ionosphere Open skies – LWA1 is funded by NSF as a University Radio Observatory

#### VLA 4-band Modified J-Poles (MJP)s

- Adds 50-80 MHz capability to the VLA
- More sensitive (wider band) than old 4-band system
- Resolution ~ 20" in A config



ea06 ea09\* ea10 ea12 ea14 ea18 ea19 ea23\* ea27\*

\* = Recent install+ 5 more soon

As of 10/30 from

Dan Mertely

9/17/2015: 3C196 6 VLA + LWA1 Raw VDIF format 35 minutes A config 72 – 80 MHz Correlated using the LWA Software Library

31 microsec offset for LWA1



#### eLWA - Bandpass



1-1-

## eLWA – Amplitude vs (u,v) distance

Edit all channels.

3C196 at 0.076 GHz in YY 2015 Sep 17

1:LWA001



3C196 Peak ~ 100 Jy Noise ~ 200 mJy SEFD ~ 8000 Jy LWA1 SEFD ~ 20 - 40 kJy



Problems:

Delays sometimes jump

53



Problems:

Delays sometimes jump Or drift



Problems:

Delays sometimes jump Or drift And this can be between VLA antennas



#### LWA-SV

- Power and Fiber installed
- 4-88 MHz frequency range
- Racks in place
- Cabling in place
- All 256 antennas deployed
- Advanced Digital Processor under development



 $10 \text{ VLITE} + LWA1 + SV_{\text{UV Coverage for svout}}$ 



#### The Long Wavelength Array



# Summary

- LWA1 has demonstrated technical feasibility and scientific results.
- $\blacktriangleright$  Lots of exciting science at low frequencies. Progress requires:
  - High temporal, spectral, and spatial resolution
  - Sensitivity
  - Software development
- Current experiments are providing new hardware and software, and a better understanding of the sky at long wavelengths
- $\blacktriangleright$  We have begun the next phase interferometry with LWA and VLA stations
- Science at Low Frequencies meeting in Albuquerque Dec 2-5, 2015



3C196



Tau A



ID	Task Name	Responsible	Start	Finish	2015 Jun Jul Aug Sep Oct Nov Dec	2016 c Jan Feb Mar Anr May Jun Jul Aug Sep Oct Nov Dec	2017 Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov De	2018 c Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
1	VLA 4-band	NRAO	6/22/2015	12/22/2017	V			, , , , , , , , , , , , , , , , , , ,
2	Validate 6 antennas VLA 4-band (Commissioning)	Frazer Owen	6/22/2015	9/21/2015				
3	VLA 4-band validated (node b in decision tree)		9/22/2015	9/22/2015	<u>_</u>			
4	Upgrade all 28 VLA antennas at 4-band	Dale Frail	9/21/2017	12/21/2017				
5	VLA 4-band complete		12/22/2017	12/22/2017				
6	Interferometry with LWA1 and VLA 4-band	UNM	9/22/2015	12/22/2015	<b>v</b>	7		
7	Fringes between VLA 4-band and LWA1 using VLITE Correlator	Greg Taylor	9/22/2015	11/2/2015				
8	Validate LW1 – VLA 4-band Interferometry (Commissioning w/o disrupting VLITE OPS)	Greg Taylor + Dale Frail	11/9/2015	12/21/2015		Ь		
9	LWA1 + VLA 4-band interferometer Validated (node f in decision tree)		12/22/2015	12/22/2015	L•			
10	Interferometry with LWA1, LWA-SV and VLA 4-Band	UNM	12/22/2015	9/22/2016	L	<b>7</b>		
11	Fringes between LWA1 & LWA-SV (UNM)	Greg Taylor	12/22/2015	3/22/2016	1			
12	Temporarily add LWA-SV with LWA1 + VLA 4-band using VLITE Correlator	Greg Taylor + Dale Frail	3/23/2016	6/22/2016				
13	Validate System in non-confusion dominated regime (Commissioning w/o disrupting VLITE OPS)	Greg Taylor + Dale Frail	6/22/2016	9/21/2016				
14	LWA1, LWA-SV and VLA 4-band Interferometer Validated (node g in decision tree)		9/22/2016	9/22/2016				
15	LOBO (VLITE Expansion)	NRL	3/21/2017	12/24/2018				
16	Upgrade VLITE Correlator to process dual 74MHz/330MHz for narrow 4P-band + LWA1, LWA-SV	Namir Kassim	3/21/2017	6/21/2017				
17	VLITE Correlator able to dual process 74/330 MHz		6/22/2017	6/22/2017			<b>↓</b>	
18	Upgrade VLITE Correlator to process full 4P-band + LWA1, LWA-SV	Namir Kassim	12/22/2017	12/21/2018				
19	LOBO CORRELATOR (able to process broadband 4P-band)		12/24/2018	12/24/2018	A D	DnC C BBnA BBnA		L



ID	Task Name	Responsible	Start	Finish
1	VLA 4-band	NRAO	6/22/2015	12/22/2017
2	Validate 6 antennas VLA 4-band (Commissioning)	Frazer Owen	6/22/2015	9/21/2015
3	VLA 4-band validated (node b in decision tree)		9/22/2015	9/22/2015
4	Upgrade all 28 VLA antennas at 4-band	Dale Frail	9/21/2017	12/21/2017
5	VLA 4-band complete		12/22/2017	12/22/2017
6	Interferometry with LWA1 and VLA 4-band	UNM	9/22/2015	12/22/2015
7	Fringes between VLA 4-band and LWA1 using VLITE Correlator	Greg Taylor	9/22/2015	11/2/2015
8	Validate LW1 – VLA 4-band Interferometry (Commissioning w/o disrupting VLITE OPS)	Greg Taylor + Dale Frail	11/9/2015	12/21/2015
9	LWA1 + VLA 4-band interferometer Validated (node f in decision tree)		12/22/2015	12/22/2015
10	Interferometry with LWA1, LWA-SV and VLA 4-Band	UNM	12/22/2015	9/22/2016
11	Fringes between LWA1 & LWA-SV (UNM)	Greg Taylor	12/22/2015	3/22/2016
12	Temporarily add LWA-SV with LWA1 + VLA 4-band using VLITE Correlator	Greg Taylor + Dale Frail	3/23/2016	6/22/2016
13	Validate System in non-confusion dominated regime (Commissioning w/o disrupting VLITE OPS)	Greg Taylor + Dale Frail	6/22/2016	9/21/2016
14	LWA1, LWA-SV and VLA 4-band Interferometer Validated (node g in decision tree)		9/22/2016	9/22/2016
15	LOBO (VLITE Expansion)	NRL	3/21/2017	12/24/2018
16	Upgrade VLITE Correlator to process dual 74MHz/330MHz for narrow 4P-band + LWA1, LWA-SV	Namir Kassim	3/21/2017	6/21/2017
17	VLITE Correlator able to dual process 74/330 MHz		6/22/2017	6/22/2017
18	Upgrade VLITE Correlator to process full 4P-band + LWA1, LWA-SV	Namir Kassim	12/22/2017	12/21/2018
19	LOBO CORRELATOR (able to process broadband 4P-band)		12/24/2018	12/24/2018

# LWA-SV

#### Construction



#### **Advanced Digital Processor**



### LWA-SV commissioning



# Natural Hazards



3C196 Peak ~ 100 Jy Noise ~ 400 mJy SEFD ~ 8000 Jy LWA1 SEFD ~ 40 - 80 kJy

