


MRO INTERFEROMETER: PRELUDE TO FIRST FRINGES





*Michelle Creech-Eakman
Project Scientist MROI
Prof. of Physics, NM Tech*

Overview of the Observatory

- 
- Magdalena Ridge about 1 hour west of Socorro, NM overlooking VLA
 - Altitude 10,500 ft
 - Env. Impact Survey completed in 2003
 - Two facilities at MRO
 - Fast-tracking 2.4m
 - NIR/Optical 10-element interferometer
 - Third site available
 - MROI is 10 1.4m movable afocal telescopes in equilateral Y configuration (28 stations)
 - Optical and near-IR operation, near-IR fringe tracking
 - Baselines from 7.8 to 347m (58 to 0.3 mas)
 - Design optimized for imaging mission

MROI Science Case

- AGN:
 - Verification of the unified model.
 - Determination of nature of nuclear/extra-nuclear starbursts.
 - $H = 14$ gives >100 targets.
- Star and planet formation:
 - Protostellar accretion, imaging of dust disks, disk clearing as evidence for planet formation.
 - Emission line imaging of jets, outflows and magnetically channeled accretion.
 - Detection of sub-stellar companions.
- Stellar accretion, mass loss and B fields/circulation:
 - Convection, mass loss and mass transfer in single and multi-star systems.
 - Bipolarity and collimation of circumstellar material, wind and shock geometries, interacting binary systems.
 - Pulsations in Cepheids, Miras, RV Tauris, etc.
 - Star spots, oblateness, asymmetric properties.



Flow Down for Requirements

- Telescope diameter of 1.4 m
 - H magnitude = 14th for group delay tracking limit
- Spatial scales of 0.3 to 58 mas
 - Baselines from 7.8 to 347 m (for 0.6-2.4 microns)
- Moderate-to-high spectral resolutions
 - Separate fringe tracking and science cameras
- High throughput to achieve sensitivity limit
 - Fifteen reflections from primary to detectors (13% throughput)
 - Optimized coatings (polarization, phase, reflectivity) for 0.6-2.4 microns
- Large number of telescopes rapidly combined/movable
 - Optimized for model-independent imaging



Photo T. Eakman, Array layout: A. Olivares

Try to apply lessons learned from other interferometric facilities whenever possible.

Team has experience with hardware at: COAST, SUSI, KI, NPOI and PTI

Telescope #1 first light 2+ years ago


- AMOS 1.4m diameter alt-alt telescopes
 - 62nm rms wavefront after 3 reflections
 - Polarization preserving design
 - Tip-tilt secondary on PI hexapod - reduce number of reflections & achieve low-order AO correction
 - First light in VCMF in Nov '16; first light on the array in '18



First Enclosure



(+Scope) on the Array

- EIE enclosures house and transport telescope
 - Squat design - 6 hours continuous tracking in close-packed configuration (7.8m on centers)
 - Louvered design for venting to equilibrate rapidly
 - Embedded metal mesh for lightning protection
 - Lifting with crane, preferably reach stacker –see movies
 - Factory Testing completed in Jan; Site Testing completed Oct '18; First light on array in Nov '18 with FTT; multiple observing runs in 2019



Telescope Primary for UT#2 Done Polishing


- 6 full sets of optics purchased a decade ago
- Secondaries and tertiaries all finished before original company went bankrupt – now at AOS
- Measured rms WFE on 2nd primary is 16.6nm (19.5nm is requirement)
- Using CGH vertically in the mirror mount to match all primaries
- Polishing of 3rd primary started 6 weeks ago
- Plan to swap out 3rd primary with 1st primary if done by Fall '20



Fast Tip-Tilt System


Closed the Loop

- Designed and built by Cambridge University
 - Passive design to minimize moving parts
 - Sensing in “blue” end of spectrum to at least $V=16$
 - Fast tip-tilt deployed on Nasmyth table controls telescope secondary
 - <60 mas 2-axis T/T jitter in Nov ‘19 on $V=12$ objects in mediocre ($1.5''$) seeing




Beam Relay System being Extended

- All designed/built at NMT
- Array infrastructure includes 28 telescope locations – 7 partially completed; 2 exterior beam lines installed on W arm
- Continuous light transport via ~ 1 mbar vacuum from telescope to beam combining room
- Designed to minimize subsidence and prevent lightning strikes from getting “into” the building
- Full-beam line light into inner BCA in fall; complete testing in a few months





Beam Combining Facility being Populated

- Completed in 2008 to support full facility including 10 delay lines and 4 instrument tables
- Continuous single stroke delay; “dead air” in beam combining room
- Tested for thermal/vibrational stability
- Installation of several tables using laser tracker



Delay Lines Trolleys Operational

- Innovative redesign compared to other facilities
- Delay line carts/trolleys – cat’s eye vacuum system designed/tested by Cambridge
- Inductive pick-up
- Compliant wheels
- Tip-tilt secondary
- Wireless to computer








Delay Line Pipes

- 190m continuous vacuum delay using off-the-shelf pipe
- Installed on a technical slab separated from outer building footings/walls
- Compensates for sidereal positions & atmospheric turbulence
- Holds vacuum (~ 1 mbar) for weeks without issue
- 2nd pipe install next month
- Trolley 2 being shipped shortly – OPD jitter < 15 nm in any 10ms interval - demonstrated in COAST DL pipes






Automated Alignment System

- End-to-end alignment of interferometer as needed during day/night
- Quad-cell photovoltaic “pop-ups” for beam location
- Optical/infrared beam launchers for “fake stars”
- BEASST WFS installed in summer ‘19
- 2nd pipe and optics line being installed shortly
- Requires beam stability/alignment at fractions of arcsecond and less than 1% of beam width throughout interferometric observation





Beam Combiner and Fringe Tracker (ICoNN)

- Nearest-neighbors style fringe tracking; DVPs for dispersion
- Beam combiner accepts all 10 beams – 5 go into each dewar
- Inner 6 beam trains tested and populated with optics
- Upgrading with SAPHIRA detector (photon-counting IR MCT array) and ESO controller this spring



First Science with FOURIER

- Simple 3-beam image plane combiner being designed by Cambridge PhD student
- Uses SAPHIRA detector + ESO controller; J, H or K at moderate spectral resolution ($R \sim 100$)
- Free-space propagation, anamorphic optics and spatial filtering with slits
- FDR at MROI in Dec '19; delivery early 2021



Potential Early Science with MROI




Fig. courtesy of S. Rinehart

Two scopes:

- Assume deeper magnitudes
- Binarity in faint systems – several different applications
- AGN reverberation mapping
- Diameters/limb-darkening of faint dwarfs/exoplanet host stars
- Stellar pulsations

Three scopes:

- Assume closure phase capability
- CVs/Novae in active phases
- Stellar rotational elongation
- Non-radial stellar pulsations
- YSO disks/openings

Funding and Fringes Timeline



Simulated image
Direct-TV
Satellite #9
accomplished in
2 hours using
10-element
MROI plus 2.4m
scope with
aperture
masking

- Funding via AFRL under CA with university for \$25M through 2021
 - Get first fringes and do GEO risk reduction demos [on this timeline](#)
- Future funding after 3 telescopes is TBD – *looking for partners, public or philanthropic support*
- Cost **~\$8.5M/beamline** for hardware – entire facility plus start-up of operations pitched to Decadal for \$110M
- Initial science after first fringes with deeper magnitudes than possible today
- Near-Term Timeline:
 - Anticipate fringes in ~12 months – late 2020/early 2021
 - 3rd UT may be ordered in a few months
 - Schedule thereafter is funding dependent
 - Delivery time for future telescope+enclosure is 15-18 months (can build in pairs)
- Anticipate making time available to astronomical community via NOAO around deployment of UT4 & 5
- 2023 AAS June meeting is in Albuquerque – anticipate MROI tours

The Extended Team:

- Van Romero – PI
- Ifan Payne – Director
- Chris Haniff & David Buscher – System Architects
- Michelle Creech-Eakman – Project Scientist
- Rob Ligon – Instrument Scientist
- Andres Olivares – Lead Mechanical Engineer
- Allen Farris – Lead Software
- NMT Team: Robert Collins, Chuck Dahl, Dipanjan Das Roy, Dylan Etscorn, Shelbi Etscorn, Colleen Gino, Omid Hosseni, Stephen Jojola, Jennie Maes, Danielle Ochoa, Juan Pino, Chris Salcido, Isaac Salayandia, Amanda Sanchez
- Cambridge Team: John Young, Bodie Seneta, David Sun, Martin Fisher
- Recent and Current Students at both: Dooley, Erica, James, Andrew, Louis, Caylin, Brandon, Mariam, Ratna, Mateo, Sarah, Elizabeth, William, Julianna, Dan, Siavash



Thank you for your attention!

*We miss our dear
friend and colleague
Dan Klingsmith*

