


---

# EVLA Feed CDR

## Outdoor Antenna Test Range (OATR)



# The OATR: Purpose




---

To support the EVLA Project by providing:

- A mechanism to monitor the feed horn manufacturing process by using:
  - VSWR measurements: All new feeds will be tested! **(100% Sampling)**
  - Radiation patterns: Statistical Sampling = 5 or 6 units from each frequency band + the first feed fabricated with new or modified manufacturing process.  
**(~20% Sampling)**
- A **long-term** troubleshooting tool!
- Future design testing platform.




# The OATR: Why a local facility?



Antenna Range Costs Comparison				
Shipping/Testing Costs @ External Testing Facility (Estimate)	Total Projected Costs for antenna range with brand new equipment:	Total Material and Equipment costs for building test range (to date):	Funds required to complete project:	New Mexico Tech contributions to completing the project:
\$93,000	\$148,510	\$13,629	\$4,100	\$6,840



# The OATR: Progress (*Highlights*)



Overall Completion:  
**51%**

Requirements: **60%**

Location: **30%**

22ft Baseline Separation	Simulating the distance between the sub-reflector and the feed circle.
14ft Elevated Platforms	To reduce potential multi-path reflection energy.
0.05deg Angular Resolution	Based on the optical encoder resolution with the systematic backlash of the positioner.
1700lb Vertical Load Capacity	Using double density polystyrene foam tower.

Tunable Frequency Range: <b>45MHz – 26.5GHz</b>	HP8510B (Rx) HP8340A (Tx)
Actual Coverage: <b>1 – 18GHz</b>	Standard Gain Horn coverage
Sensitivity: <b>-70dBm</b>	<b>Estimate only!</b> Based on acquired radiation pattern data.
Amplitude Repeatability: <b>~ 1.5dB</b>	Refinement still in progress!




# The OATR: Capabilities (*Generalized*)



- Amplitude and Phase measurements.
- Time-Gating with pico-second resolution.
- Gain normalization.
- Phase Center measurements.
- Axial ratio / Polarization measurements.




# The OATR: The Site!






# The OATR:

## Proof of Concept Setup






---

(Intentionally left blank)





# The OATR: Progress *(Detailed)*





Established Requirements and Progress

Requirement	Minimum Requirement	Goals	Status	Notes / Comments
System Automation	Manual	Computer	Complete	Computer Controlled
Tunable Frequency	1 to 8 GHz	1 to 12 GHz min.	Exceeded	45MHz to 26 GHz Possible
Receiver Type	Scalar (amp)	Vector (amp &	Complete	Vector (HP8510B)
Amplitude Accuracy	< 1 dB	< 1 dB	In Progress	Initial results <2dBm with response calibration. Testing in progress.
Phase Accuracy	n/a	TBD	In Progress	Will be identified after permanent location established
Sensitivity (1 KHz	< 60 dBm	< 60 dBm	In Progress	Testing in progress.
Source Output	< +10 dBm	< +10 dBm	Complete	Stable output at various levels
Nominal Tx	~ 40 deg.	~ 40 deg.	In Progress	New Standar Gain Horns require further evaluation.
Nominal Tx Gain	>12 dBi	>12 dBi	Complete	11.5 to 23 dBi typical for Gain Horns.
Range Type	Elevated (10 ft)	Elevated (22 ft.)	In Progress	Elevated (14ft)
Range Length (R)	22 ft (fixed)	Up to 200 ft	Complete	Established 22ft Separation
Clutter Free Range	> (3*R)^2 sq. ft	> (3*R)^2 sq. ft	In Progress	Location depenant item.
AUT Vertical Load	1000 lbs.	1000 lbs.	Exceeded	>1100lbs achieved with High Density Foam Column Tower.
AUT Moment	1000 ft. lbs.	1000 ft. lbs.	Complete	1000lbs
Angular Accuracy	< 0.1 deg.	< 0.1 deg.	Complete	0.05 deg with systematic backlash included.



# The OATR: Reflections





# The OATR: Boresight (Electrical)

