



# Fiber Installation Preliminary Design Review


December 5, 2001



# IF Signal Path




• = One Fusion Splice  
1





# Cable Installation



The IF system parameters were major factors in selecting fiber.

The LO system parameters are major factors in selecting an installation method.



# Burial Depth


## Determined by LO phase stability



- LO system requires phase stability.
  - Stability determined partly by fiber thermal expansion
  - Fiber in ground contributes to total expansion.
  - Expansion determined by ground temperature
  - LO short term stability must be  $< 0.5$  ps in 1 sec.
  - LO long term stability must be  $< 1.4$  ps in 30 min.



# Burial Depth LO Parameters




- Highest transmitted LO is 500 MHz
- Period of 500 MHz is 2000 ps
- Wavelength of 500 MHz in fiber is 40 cm



# Burial Depth

## Fiber Thermal Expansion



- Coefficient of expansion of fiber =  $18 \times 10^{-7} /^{\circ}\text{C}$   
( From F. Quan, Corning, Inc. )
- Average annual temp. variation at 1 m =  $17.4 ^{\circ}\text{C}$ .  
( See EVLA Memo 10 by T. Cotter )



# Burial Depth


## Fiber Thermal Expansion



- Assuming:
    - A linear average rate of temperature change
- $\Delta L = (18 \times 10^{-7} /{^\circ}\text{C})(17.4 \text{ } {^\circ}\text{C/yr})(22 \text{ km})$   
= 68 cm over 180 days  
=  $7.9 \times 10^{-3}$  cm in 30 min  
=  $4.4 \times 10^{-6}$  cm in 1 sec



# Burial Depth LO Phase Instability



- Long Term LO phase stability in the ground

$$\begin{aligned}\text{Stability} &= (2000 \text{ ps}) ( 7.9 \times 10^{-3} \text{ cm in 30 min} ) / ( 40 \text{ cm} ) \\ &= 0.395 \text{ ps in 30 min} \quad \ll 1.4 \text{ ps}\end{aligned}$$


- Short Term LO phase stability in the ground

$$\begin{aligned}\text{Stability} &= (2000 \text{ ps}) ( 4.4 \times 10^{-6} \text{ cm in 1 sec} ) / ( 40 \text{ cm} ) \\ &= 0.00022 \text{ ps in 1 sec} \quad \ll 0.5 \text{ ps}\end{aligned}$$



# Burial Depth

## Antenna Fiber



- Assuming  $L = 20\text{m}$ ,  $\Delta t = 10\text{C}$ ,  $\Delta L = .036 \text{ cm}$
- Long Term LO phase stability on the antenna  
Stability =  $(2000 \text{ ps}) ( .036 \text{ cm in } 30 \text{ min }) / ( 40 \text{ cm} )$   
 $= 1.8 \text{ ps in } 30 \text{ min}$       NOT  $\ll 1.4 \text{ ps}$
- Short Term LO phase stability on the antenna  
Stability =  $(2000 \text{ ps}) ( 2.0 \times 10^{-5} \text{ cm in } 1 \text{ sec } ) / ( 40 \text{ cm} )$   
 $= 0.001 \text{ ps in } 1 \text{ sec}$        $\ll 0.5 \text{ ps}$



# Burial Depth Summary




- One meter burial depth is sufficient.
- Contribution of the buried fiber to the LO system instability is small.
- Contribution of fiber on antenna structure is a greater concern.



# Cable Burial Plan


## Fiber Acceptance Test



- Every fiber to be tested upon delivery.
- Every fiber to be tested after installation.
- Acceptance specification to be developed.




# Cable Burial Plan






# Basic Cabling Plan





# Cable Burial Plan

## Trunks





Cable ID	Service for Pads	Destination	Fiber Count
<b>East Trunks</b>			
TY	DN1,DW1,DE1,DE2,DE3	DW1	60
TDE	DE4,DE5,DE6,DE7,DE8,DE9	DE4	72
TCE	CE5,CE6,CE7,CE8,CE9	CE5	60
TBE	BE5,BE6,BE7,BE8,BE9	BE5	60
TAE	AE5,AE6,AE7,AE8,AE9	AE5	60
<b>West Trunks</b>			
TDW	DW2,DW3,DW4,DW5,DW6	DW6	60
TCW	DW7,DW8,DW9,CW5,CW6,MP	DW7	72
TBW	CW7,CW8,CW9,BW5,BW6,BW7,BW8,BW9	CW7	96
TAW	AW5,AW6,AW7,AW8,AW9	AW5	60
<b>North Trunks</b>			
TDN	DN2,DN3,DN4,DN5,DN6,DN7,DN8,DN9	DN2	96
TCN	CN5,CN6,CN7,CN8,CN9	CN5	60
TBN	BN5,BN6,BN7,BN8,BN9	N. of RT. 60	60
TAN <sup>2</sup>	AN5,AN6,AN7,AN8,AN9	AN5	60



# Cable Burial Plan

## Direct Burial Splice Box





# Cable Burial Plan

## Cable Type



- Armor protects the fiber from
  - Rodents
  - Crushing forces
- Armor - lightning protection issue
  - Armor must be grounded
- First layer of armor is sacrificial
  - Double armor is required



# Cable Burial Plan


## Cable Cross Section






# Cable Burial Plan

## Grounding





- Bonded to ground at every connection.
  - Bonded with 8 AWG copper, minimum.
  - Bonded to antenna ground, control building ground, or a ground rod.






# Antenna Termination Antenna Pad Enclosure






# Antenna Termination Antenna Junction Box






# IF Signal Path




• = One Fusion Splice  
1






# CB Main Distribution Frame






# CB Main Distribution Frame Termination Panel





# CB Main Distribution Frame Termination Panel



- Provisions for 876 fibers ( 73 Pads )
- Stores extra fiber for maintenance
- Space available for expansion to 1200 fibers





# CB Main Distribution Frame



## Cable Type Required



- Plenum Cable Type OCNP is required in building
- 30-Fiber tight buffer cables will be used
  - Twenty-one cables required
  - Cables organized by array arm and system



# CB Main Distribution Frame Patch Panels





# Fiber Installation

## Work Yet to be Accomplished



- Lightning protection
  - What material will not react with the existing cathodic protection system? Copper?
- Further development of CB fiber plan
- Further development of Antenna cabling
  - How will the cable wrap effect LO stability?
- Develop Installation Specification .
- CDR




# Cable Burial Plan Summary



- 13 Trunk Cables from CB out to the Array.
  - 60, 72 and 96 fiber cables.
  - Triple Jacket/ Double Armor.
  - Standard single-mode fiber.
- 17 splice locations
- 12-fiber cable from trunks to antennas.
- Acceptance Test before and after installation.



# Cable Burial Plan Summary



- Trenched & Installed by ES Division
- Spliced and terminated by Electronics Division
- Burial Depth - one meter minimum.
- Cable identified with marker tape.
- Splices identified with a concrete monument.
- Armor grounded at each splice or termination.



# Next Topic

