




# Fiber Tasks

## Preliminary Design Review

December 5, 2001



# CB Main Distribution Frame






# Patch Panels



- Similar to Termination Panel
- Located throughout the Control building





# Phone System

- Two phones per antennas,
  - Vertex room and Pedestal
- Phone numbers remain with the antenna
- Will use the fiber system
- Will use COTS hardware
  
- Responsible for providing the Fiber from the Termination panel to Phone Room



# Battery Backed-up Communication



- Similar to VLA WYE Monitor
- Un-interruptible power supply



# MCB Network



- Standard Ethernet ( two Fibers )
- COTS Network Router
- 1 Gbit/s to antennas
- 100 Mbit/s in the antennas
- Support ~48 nodes in each antenna
  - Two multi-mode fibers per node
  - Fiber to the Module
- Patch Panel will be located in the computer room



# LO System

- Responsible for Lasers, Modulators, Fiber, Circulators, Receivers
  - Maybe integrated into the LO module
  - Phase stable system
- LO Patch panel
  - located in the Electronics Room
  - Fiber test equipment
- System Self-tests included



# IF System



- Transmitters
- MUX-Fiber-DeMUX components
- Fiber Amplifiers
- Receivers
- Online monitoring





# IF Transmitters



- Twelve Lasers – ITU spacing
- Automated Test
  - Output Power Measured at Each Laser ( 1% tap)
  - MCB accessible
- Manual Optical Power Measurements
  - Can be measured at the MUX output



# IF Patch Panel



- Located in the Correlator room
- Includes De-MUX hardware
- Includes Fiber Amplifiers
  
- Manual Test Equipment
  - Full Signal Communication Analyzer



# Rack Mount EDFA



- MCB adjusted Gain of each amplifier
- Also measures in/out optical power





# IF Communication Analyzer



- IF Patch Panel
  - Manual measurements during reconfiguration
- Complete Diagnostic
  - Jitter
  - Q Factor
  - Noise Margin
  - Rise / Fall times




# IF System On Board Tests



- Test Patterns Generated at each Transmitter
- Nine Test Patterns
  - No Sync, alternating 1/0, all Ones, all Zeros
  - Parity Errors
- MCB controlled



# Proposed Frame Format



- EVLA Memo #33




# Divided Sync Word

- Required to Identify Correct 1/2 Sequence
- 10 Bits long,
  - 6 bit identify Start-of-Frame
  - Barker Sequence - equal Ones versus Zeros
- Three Stage Synchronization Process



# Sync Implementation







# Three Stage Synchronization

- Stage 1 - Search bits for frame pattern
- Stage 2 – Monitor for “Correct” sync
- Stage 3 – If two “Bad” frames in a row  
or 2-out-of-8 frames are “Bad”

Then Start Search Again



# Timing Signals



- Metaframe Index
- Metaframe Sequence Count
- 1 PPS
- 1 Pulse per 10 seconds



# Data Valid Signal



- Initiated at the antenna
  - Toggle Switch
  - MCB controlled
- Passed to correlator



# Check Sum - BER

- Each 19 bits Generate a check Sum
- Provides continuous Bit-Error-Rate Performance Monitoring
- Only odd # of errors per 19 bits Detected
- Flags Correlator when over threshold



# Scrambling

- Frame Synchronous Scrambling
  - Select pattern is modulo 2 added
  - Entire frame – except sync bits
- Pattern results in
  - Equal number of Ones/Zeros providing
    - Balance ac content, sufficient transitions
    - Minimize low frequency content



# Conclusion

- Five systems will be supported
- On Board Tests Incorporated ( MCB)
- Patch Panels will have test equipment
- IF Data Format will support Growth



# Next Topic





# IF Signal Path

